



NOTES:

1. ABOVE GROUND INSTALLATION PREFERRED. UNIT MAY BE INSTALLED BELOW GROUND IF DRAINAGE ENSURES UNIT WILL NOT BE SUBMERGED.
2. PIPE LINE SHALL BE FLUSHED BEFORE UNIT IS INSTALLED.
3. MOUNT UNIT IN UPRIGHT POSITION IN A HORIZONTAL PIPE RUN. INSTALL SUPPORTS PER MANUFACTURER RECOMMENDATION.
4. ALLOW CLEARANCE AROUND UNIT TO CONDUCT TESTS AND REPAIRS.
5. NEW INSTALLATION SHALL BE INSPECTED AND TESTED BY LICENSED BACKFLOW PREVENTION TESTER
6. ENSURE TEST COCK PLUGS ARE INSTALLED SECURELY AND ARE LEAK PROOF.

HYDE PARK CITY

113 EAST CENTER
HYDE PARK, UTAH 84318
TEL. (435) 563-6507



**DOUBLE CHECK VALVE
BACKFLOW PREVENTION
(SURFACE)**

CW-05

DATE: 02-09-21