



1. INSPECTION: PRIOR TO BACKFILLING AROUND THE ASSEMBLY, SECURE INSPECTION OF INSTALLATION BY ENGINEER.
2. BACKFILL: INSTALL AND COMPACT BACKFILL MATERIAL PER APWA SECTION 02320.
3. CONCRETE: CLASS 4,000 PER APWA SECTION 03304. APPLY A SEALING/CURING COMPOUND PER APWA SECTION 03390.
4. WORKING PARTS: ALL WORKING PARTS SHALL BE BRONZE-TO-BRONZE DESIGN, AND BE SERVICEABLE FROM ABOVE GROUND WITH NO DIGGING.
5. POST HYDRANTS: SHALL BE NON-FREEZING, SELF DRAINING TYPE WITH A 36" BURY. HYDRANTS WILL BE FURNISHED WITH A 2" FIP INLET, A NON-TURNING OPERATING ROD, AND SHALL OPEN TO THE LEFT.
6. LOCKING: HYDRANTS SHALL BE LOCKABLE TO PREVENT UNAUTHORIZED USE AS MANUFACTURED BY KUPFERLE FOUNDRY CO., ST. LOUIS, MO., OR APPROVED EQUAL.

HYDE PARK CITY

113 EAST CENTER
HYDE PARK, UTAH 84318
TEL. (435) 563-6507



BLOW-OFF HYDRANT

CW-13

DATE: 02-09-21